VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

Basic – Rs. 2,199.00 / Sq.Ft

- RCC Framed Structure
- RCC Foundation & Roof
- Price may vary depending no. of floors

Design

- 2D Floor Plan
- Structural Designing
- Electrical & Plumbing Drawing 2D
- Elevation Design

Structure

- Basement height: Upto 2 feet
- Steel: Any ISI brand- Upto 57/kg
- Aggregates: 20mm & 40mm
- Blocks: 6 inch for Exterior Wall & 4 inch for Interior Wall or
- Bricks: 9 inch for Exterior Wall & 4.5 inch for Interior Wall (Rs.20/sft extra during rainy season due to increase in bricks price)
- Cement: Any ISI brand- Upto 270/bag
- M Sand: Blockwork & P Sand: Plastering
- RCC Design Mix: M20
- Ceiling Height: 10 Feet

Kitchen

- Ceramic Wall Tiles 2 Feet Above Kitchen Slab Upto 35 Per Sq ft
- Main Sink Faucet Upto 1500 & ISI Marked
- Kitchen Sink: Stainless Steel Upto 2000 Rs
- Kitchen Granite Slab: 20 mm Thick Upto 80 Rs per Sq ft

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

Bathroom

- Wall Tiles For 7 Feet Upto 35 Rs Per Sq ft
- Sanitary Ware & CP Fitting Upto Rs 10,000.
- Inner CPVC/Outer PVC: Any ISI brand
- Bathroom Accessories: EWC, Health Faucet, Wash Basin, 2 in 1 Wall Mixer, Overhead Shower
- All bathroom fittings are white color & basic model in any ISI brand
- PVC Door & Frame

Plumbing

Plumbing Points

- **Bathroom –** 1 wash basin with tap, 1 shower with wall mixer for hot & cold water, 1 floor mount western closet with health faucet.
- **Dining –** 1 wash basin with tap
- **Kitchen –** Single stainless steel sink with 1 tap.
- **Service –** 1 tap point & water outlet point for washing machine

Doors & Windows

- Main Door: Ready Made Basic Teak Door With Teak Wood Frame of 5 Inch by 3 Inch, 38mm Thickness
- Internal Door: Flush Door With Laminates Along With Sal Wood Frame of 4 Inch by 3 Inch
- Windows: Standard aluminium 2 Track sliding window

Door sizes:

- Main Door – 3.5’(Width) X 7’(Height)
- Rooms – 3’(Width) X 7’(Height)
- Bathroom & Balcony – 2.5’(Width) X 7’(Height)
- Window size – 4’(Width) X 4’(Height) (1 window per room)

Painting

- Interior:
    - 1 coat of Asian brand putty

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- 2 coats of Asian Tractor emulsion paint for the walls (light colours)
- 1 coat of primer and 2 coats of Asian Tractor emulsion paint for the ceiling

- Exterior:
  - 1 coat of Asian primer
  - 1 coat of white cement
  - 2 coats of Asian Ace emulsion paint (light colours)

Flooring

- Living & Dining Flooring: Tiles Upto 45 Rs Per Sq ft
- Room & Kitchen Flooring: Tiles Upto 45 Rs Per Sq ft
- Balcony & Open Area Flooring: Tiles Upto 35 Rs Per Sq ft
- Staircase Flooring: Anti-skid Tiles Upto 35 Rs Per Sq ft
- Parking Tiles: Anti-skid Tiles Upto 35 Rs Per Sq ft

Electrical

- Wires – Any ISI brand
- Switches – Orbit

Electrical Points

- **Bedroom** – 1 switch box with switches for 1 fan, 2 lights and 1 five amps socket with switch near door and another switch box with same set of switches near bed for two-way control.
  1 AC point, 1 fan point and 2 lights point
- **Bathroom-** 1 switch box with 1 switch for light and 1 switch for heater near the door & 15 amps socket for heater. 1 switch box with 1 five amps socket for hair dryer near the mirror
- **Hall-** 1 switch box near the door for 2 fans, 2 lights & 1 five amps socket and another switch box with same set of switches near sofa. 1 switch box with 1 five amps sockets and switches along with cable point for TV connection
- **Dining-**1 switch box with switches for 1 fan & 1 light
- **Pooja-** 1 switch box with switch for 1 light

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- **Kitchen-** 1 switch box with switch for 2 lights, 1 exhaust fan. 1 switch box with 15 amps socket & switch for refrigerator. 1 switch box with one 15 amps socket & switch for mixie/ oven.
- **Service-**1 switch for light, 1 switch box with 15 amps socket & switch for washing machine

Other Inclusives

- Parapet wall upto 3 feet high (included if headroom is built)
- Staircase Railing: MS Railing
- 2D Floor Plan
- Structural Designing
- Electrical and Plumbing Drawings
- Elevation Design

Lofts & Shelves:

- 1 Loft in each bedroom, kitchen & pooja room on the shorter side of the wall
- 1 Shelf in each bedroom, kitchen & pooja room of maximum width 5 feet

Extra Charges

- Compound Wall @ 410/sq.ft
- Lift
- Roof weathering
- Carpentry & other wooden work
- EB Connections & Charges
- Govt. approval charges
- Water Connections & Charges
- Underground water storage Sump Rs 25 Per Litre
- Overhead sintex tank Rs.15 per litre
- Overhead concrete tank Rs 30 per litre
- Septic Tank Rs 20 per litre
- Gates
- Elevation Work Extra
- Additional foundation height

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- Soil testing
- Interior 3d View or Walkthrough
- 3D elevation designing
- Rainwater harvesting
- Outer area development (setback)
- Anti- Termite treatment
- Any Sunken flooring will be Additional Cost
- Pile Foundation

Standard – Rs. 2,399.00 / Sq.Ft

Design

- All Features in Basic Package [Price may vary Depending no. of floors]
- 2D Floor Plan
- 3D Elevation Design
- Structural Designing
- Electrical and Plumbing Drawings

Structure

- Basement height: Upto 3 feet
- Steel: ARS or SAIL
- Aggregates: 20mm & 40mm
- Blocks: 6 inch for Exterior Wall & 4 inch for Interior Wall or
- Bricks: Chamber Bricks 9 inch for Exterior Wall & 4.5 inch for Interior Wall (Rs.20/sft extra during rainy season due to increase in bricks price)
- Cement: Coromandal and Chettinad or Dalmia

Veeru Kannamma

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- M Sand: Blockwork & River Sand: Plastering
- RCC Design Mix: M20
- Waterproofing: Dr.Fixit
- Ceiling Height: 10 Feet

Kitchen

- Ceramic Wall Tiles 2 Feet Above Kitchen Slab Upto 50 Per Sqft
- Main Sink Faucet Upto 2000 & ISI Marked
- Kitchen Sink: Stainless Steel Upto 3000 Rs
- Kitchen Granite Slab: 20 mm Thick Upto 120 Rs per Sqft

Bathroom

- Wall Tiles For 7 Feet Upto 45 Rs Per Sqft
- Sanitary Ware & CP Fitting Upto Rs 15,000
- Inner CPVC/Outer PVC: Ashirwad/Supreme/Astral
- Bathroom Accessories: EWC, Health Faucet, Wash Basin, 2 in 1 Wall Mixer, Overhead Shower
- All bathroom fittings are white color in parryware
- WPC Door & Frame

Plumbing

<u>Plumbing Points</u>

- **Bathroom –** 1 wash basin with tap, 1 shower with wall mixer for hot & cold water, 1 floor mount western closet with health faucet.
- **Dining –** 1 wash basin with tap
- **Kitchen –** Double stainless steel sink with 2 taps. 1 RO point

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- **Service –** 1 tap point & water outlet point for washing machine

Doors & Windows

- Main Door: Ready Made Malaysian Teak Door With Teak Wood Frame of 5 Inch by 3 Inch, 38mm Thickness
- Internal Door: Flush Door With Laminates Along With SG Teak Wood Frame of 4 Inch by 3 Inch
- Windows: Standard aluminium 2 Track sliding window with powder coating to the required colour / UPVC sliding windows (white color)/ 5mm clear Glass

Door sizes:

- Main Door – 3.5'(Width) X 7'(Height)
- Rooms – 3'(Width) X 7'(Height)
- Bathroom & Balcony – 2.5'(Width) X 7'(Height)
- Window size –No Restriction on Size / 1 window per room)

Painting

- Interior:
    - 2 coats of Asian/ Birla putty
    - 1 coat of primer and 2 coats of Nippon Pro Matex Gold emulsion paint for the walls (light colours)
    - 1 coat of primer and 2 coats of Nippon Pro Matex Gold emulsion paint for the ceiling
- Exterior:
    - 1 coat of primer

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- 1 coat of white cement
- 2 coats of Nippon weather bond PRO (light colours)

Flooring

- Living & Dining Flooring:Tiles Upto 55 Rs Per Sqft
- Room & Kitchen Flooring: Tiles Upto 55 Rs Per Sqft
- Balcony & Open Area Flooring: Tiles Upto 45 Rs Per Sqft
- Staircase Flooring: Anti-skid Tiles Upto 45 Rs Per Sqft
- Parking Tiles: Anti-skid Tiles Upto 45 Rs Per Sqft

Electrical

- Wires – Finolex
- Switches – Anchor Roma

Electrical Points

- **Bedroom** – 1 switch box with switches for 1 fan, 2 lights and 1 five amps socket with switch near door and another switch box with same set of switches near bed for two-way control.

1 AC point, 1 fan point and 2 lights point

- **Bathroom-** 1 switch box with 1 switch for light and 1 switch for heater near the door & 15 amps socket for heater. 1 switch box with 1 five amps socket for hair dryer near the mirror
- **Hall-** 1 switch box near the door for 2 fans, 2 lights & 1 five amps socket and another switch box with same set of switches near sofa. 1 switch box with 2 five amps sockets and switches along with cable point for TV connection
- **Dining-**1 switch box with switches for 1 fan & 1 light
- **Pooja-** 1 switch box with switch for 1 light

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- **Kitchen-** 1 switch box with switch for 2 lights, 1 exhaust fan. 1 switch point for chimney. 1 switch box with 15 amps socket & switch for refrigerator. 1 switch box with two 15 amps socket & switch for mixie/ oven.
- **Service-**1 switch for light, 1 switch box with 15 amps socket & switch for washing machine
- **Extras –** One 5 amps switch & socket for computer

Other Inclusives

- Overhead Tank: 1000 litres Sintex
- Staircase Railing: SS 304g
- Parapet Wall 3 Feet High (included if headroom is built)
- Roof weathering is included if the build-up area is more than 2000 sft.
- Rainwater harvesting
- 2D Floor Plan
- 3D Elevation Design
- Structural Designing
- Electrical and Plumbing Drawings 2D

Lofts & Shelves:

- 1 Loft in each bedroom, kitchen & pooja room on the shorter side of the wall
- 1 Shelf in each bedroom, kitchen & pooja room of maximum width 5 feet

Extra Charges

- Compound Wall @ 410/sq.ft
- Lift
- Carpentry & other wooden work

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- EB Connections & Charges
- Govt. approval charges
- Water Connections & Charges
- Underground water storage Sump Rs 25 Per Litre
- Overhead concrete tank Rs 30 per litre
- Septic Tank 20 per litre
- Gates
- Elevation Work Extra
- Additional foundation height
- Soil Testing
- Interior 3D view or walkthrough
- Outer area development (setback)
- Anti- Termite Treatment
- Any Sunken flooring will be additional Cost
- Pile Foundation

Veeru Kannammal

Premium - Rs. 2,599.00 / Sq.Ft

Design

- All Features in Standard Package [price may vary depending on no. of floors]
- Soil Testing
- 2D Floor plan
- Structural Designing

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- Furniture Layout 2D
- Electrical & Plumbing Drawing 2D
- 3D Elevation Design
- Interior 3D view or Walkthrough

Structure

- Basement height: Upto 4 feet (if required)
- Steel: Tata, JSW
- Aggregates: 20mm & 40mm
- Blocks: 6 inch for Exterior Wall & 4 inch for Interior Wall or
- Bricks: Wirecut Bricks- 9 inch for Exterior Wall & 4.5 inch for Interior Wall (Rs.20/sft extra during rainy season due to increase in bricks price)
- Cement: Ramco / Ultratech / Coromandel / Dalmia
- M Sand: Blockwork & River Sand: Plastering
- RCC Design Mix: M20
- Waterproofing: Dr.Fixit
- Ceiling Height: 10 Feet

Kitchen

- Ceramic Wall Tiles 2 Feet Above Kitchen Slab Upto 55 Per Sqft
- Main Sink Faucet Upto 2500 & ISI Marked
- Kitchen Sink: Quartz Sink With Drain Upto 5000 Rs
- Kitchen Granite Slab: 20 mm Thick Upto 160 Rs per Sqft

Bathroom

- Wall Tiles Upto Ceiling (full wall height) Upto 55 Rs Per Sqft

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- Sanitary Ware & CP Fitting Upto Rs 22,000 per Bathroom
- Inner CPVC/ Outer PVC: Ashirwad/Supreme/Astral/ Finolex
- Bathroom Accessories: EWC, Health Faucet, Wash Basin, 2 in 1 Wall Mixer, Overhead Shower
- All bathroom fittings are white color & basic model in jaquar
- Water Proof Door with Designer Laminates

Plumbing

Plumbing Points

- **Bathroom –** 1 wash basin with tap, 1 shower with wall mixer for hot & cold water, 1 floor mount western closet with health faucet.
- **Dining –** 1 wash basin with tap
- **Kitchen –** Single Bowl Quartz sink with 1 tap. 1 RO point
- **Service –** 1 tap point & water outlet point for washing machine

Doors & Windows

- Main Door: Ready Made First Quality Ghana or Indian Teak Door With First Quality Teak Wood Frame of 5 Inch by 3 Inch, 38mm Thickness
- Internal Door: Flush Door With Laminates Along With Teak Wood Frame of 4 Inch by 3 Inch
- Windows: Standard aluminium 3 Track sliding window with mosquito mesh & powder coating to required color / UPVC Open type windows (white color) / 5mm clear Glass

Door sizes:

- Main Door – 3.5’(Width) X 7’(Height)
- Rooms – 3’(Width) X 7’(Height)

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- Bathroom & Balcony – 2.5'(Width) X 7'(Height)
- Window size – No Restriction on Size & Quantity

Painting

- Interior:
    - 2 coats of Birla putty
    - 1 coat of Asian primer and 2 coats of Asian Premium emulsion paint for the walls (light colours)
    - 1 coat of primer and 2 coats of Asian Premium emulsion paint for the ceiling
- Exterior:
    - 1 coat of weatherproof primer
    - 1 coat of white cement
    - 2 coats weatherproof emulsion paint (light colours)
    - Grills: 2 coat Enamel over 1 coat primer

Flooring

- Living & Dining Flooring: 4'X2' Vitrified Tiles Upto 100 Rs Per Sqft
- Room & Kitchen Flooring: 4'X2' Vitrified tiles Upto 100 Rs Per Sqft
- Balcony & Open Area Flooring: Tiles Upto 55 Rs Per Sqft
- Staircase Flooring: Anti-skid Tiles Upto 55 Rs Per Sqft
- Parking Tiles: Anti-skid Tiles Upto 55 Rs Per Sqft

Electrical

- Wires – Finolex
- Switches – Legrand or GM

Electrical Points

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- **Bedroom** – 1 switch box with switches for 1 fan, 2 lights and 1 five amps socket with switch near door and another switch box with same set of switches near bed for two-way control.

1 AC point, 1 fan point and 2 lights point

- **Bathroom-** 1 switch box with 1 switch for light and 1 switch for heater near the door & 15 amps socket for heater. 1 switch box with 1 five amps socket for hair dryer near the mirror
- **Hall-** 1 switch box near the door for 2 fans, 2 lights & 1 five amps socket and another switch box with same set of switches near sofa. 1 switch box with 3 five amps sockets and switches along with cable point for TV connection
- **Dining-**1 switch box with switches for 1 fan & 1 light
- **Pooja-** 1 switch box with switch for 1 light
- **Kitchen-** 1 switch box with switch for 2 lights, 1 exhaust fan. 1 switch point for chimney. 1 switch box with 15 amps socket & switch for refrigerator. 1 switch box with three 15 amps socket & switch for mixie/ oven.
- **Service-**1 switch for light, 1 switch box with two 15 amps socket & switch for washing machine (one in the top & on in the bottom)
- **Extras-** 1 additional switch 7 socket in each room for mobile charging, 5amps socket & switch for computer

Other Inclusives

- Overhead Tank: 2000 litres Sintex
- Staircase Railing: SS 304g railing
- Parapet Wall 3 Feet Hight and width 4.5 inch (included if headroom is built)
- Roof weathering is included if the build-up area is more than 2000 sft.

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- Grill work: MS safety grill gate for main door & Terrace only (using 10mm M.S square & flats.
- Soil testing
- 2D Floor Plan
- 3D Elevation Design
- Structural Designing
- Interior 3D View or Walkthrough
- Furniture layout 2D
- Rain water harvesting
- Anti- Termite Treatment

Lofts & Shelves:

- 1 Loft in each bedroom, kitchen & pooja room on the shorter side of the wall
- 1 Shelf in each bedroom, kitchen & pooja room of maximum width 5 feet

Extra Charges

- Compound Wall @ 410/sq.ft
- Lift
- Carpentry & other wooden work
- EB Connections & Charges
- Govt. approval charges
- Water Connections & Charges
- Underground water storage Sump Rs 25 Per Litre
- Overhead concrete tank Rs.30 per litre
- Septic Tank 20 per litre

Veeru Kannammal

VEERU KANNAMMAL CONSTRUCTIONS SPECIFICATION

- Gates
- Elevation Work Extra
- Additional foundation height
- Outer area development (setback)
- Pile Foundation

Veeru Kannammal